



NOTICE TO PROCEED

TAUKAN ZACARIAS MATO
MUST ENTERPRISES
Gang, Sultan Kudarat (Nuling),
Shariff Kabunsuan, ARMM

Dear Mr. Mato,

Having entered into a contract with the Department of Agriculture, RFO 12, Koronadal City, please be advised that you may now proceed with the project entitled **Construction of 1 Unit Kanibong Diversion Dam** in the amount **Forty-Nine Million Two Hundred Ninety-Nine Thousand Twenty-Three Pesos and 38/100 (Php49,299,023.38)** with **ITB Reference No. 4523532**, subject to the terms and conditions of the contract agreement specifically the provision on "LIQUIDATED DAMAGES" (LD) as stipulated under RA 9184 with the following scope of works:

A. Project Description:

a. Dam Works

- Dam Length = 23.00 m
- Dam Height = 2.00 m

b. Irrigation Works (Canalization & Canal Structure)

- Main Canal A: L = 2,223.00 m
- Lateral A: L = 640.00 m
- Lateral B: L = 1,093.00 m
- Sub-Lateral D: L = 569.00 m
- Canal H: L = 1,400.00 m
- Main Canal B: L = 958.25 m
- Lateral D: L = 1,800.00 m
- Lateral F: L = 650.00 m
- Lateral G: L = 977.00 m

c. Closed Conduit

- Length = 392.00 m

d. Access Road

- Length = 300 meters, graveling

B. Scope of Work:

Item 100 - Cleaning & Grubbing: 5,300.00 sq.m.

Item 102 (2) - Excavation (Common Soil) Irrigation Canal: 3,221.60 cu.m.

Item 102 (3) - Surplus Rock Excavation: 1,071.60 cu.m.

Item 104 (2) - Selected Borrow for Topping Case - I: 6,376.20 cu.m.

Item 405 (1) a - Structural Concrete Class A (Diversion Dam): 225.48 cu.m.

Item 405 (1) b - Structural Concrete Class A (Closed Conduit and Canal Structures)

Canal Structures: 546.46 cu.m.

Item 405 (2) - Structural Concrete Class B (Canal Lining): 2,441.80 cu.m.

Item 500 (1) - Pipe Culverts for Road-xing (30'Ø): 14.00 pc




Republic of the Philippines
DEPARTMENT OF AGRICULTURE
Regional Field Office XII
Office of the Bids and Awards Committee (BAC)
Regional Government Center, Carpenter Hill,
Koronadal City, South Cotabato
Telefax No. (083) 228-3411

Item 500 (2) - Pipe Culverts for Road-xing (24'Ø): 15.00 pc
Item 500 (3) - Pipe Culverts for Road-xing (18'Ø): 8.00 pc
Item 505 (5) - Grouted Riprap, Class A: 165.60 cu. m.
Item 507 - Rubble Concrete/Masonry: 379.00 cu. m.
Item 404 - Reinforcing steel bar, Grade 40: 140,671.15 kg
SPL 1 - Concrete signage w/ DA logo and Markings: 1.00 pc
SPL 2 - Gravel Blanket: 999.27 cu.m.
SPL 3 - Flashboard: 241.00 set
SPL 4 - Installation of sliding steel gate: 18.00 assy
SPL 5 - Gabions: 192.00 pcs
SPL 6 - Lean Concrete: 14.40 cu.m.
SPL 7 - Access Road: 300.00 lm


Project Duration: Four Hundred Ten (410) Calendar Days
Project Location: Brgy. Kanibong, Tulunan, North Cotabato

Done this ___ day of SEP 18 2017 2017 at Koronadal City, Philippines.

Very truly yours,


MILAGROS CAPAO-AN CASIS, CE
Head of the Procuring Entity
Regional Executive Director

Conformed (Per Item 2 of JVA):


ROGER A. RIVERA
Robert General Mdse.
Date September 18, 2017