



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
Regional Field Office XII
Office of the Bids and Awards Committee (BAC)
Regional Government Center, Carpenter Hill,
Koronadal City, South Cotabato
TeleFax No. (083) 228-3411

NOTICE TO PROCEED

CHARLITO O. SOLONGON, SR.

Proprietor
CS Construction and Supply
Gen. Siongco St., Kalawag II,
Isulan, Sultan Kudarat

Sir:

Having entered into a contract with the Department of Agriculture RFO 12, Koronadal City, please be advised that you may now proceed with the implementation of the project entitled "**Concreting of Minapan Farm To Market Road (FMR) Phase 1** located At Tulunan, North Cotabato" in the amount of **Seven Million Seven Hundred Nineteen Thousand Four Hundred Seventy Seven Pesos and 44/100 (Php7,719,477.44)** with **ITB Reference No. 4242463** subject to the terms and conditions of the contract agreement particularly the provision on "LIQUIDATED DAMAGES" (LD) as provided under RA 9184 with the following specifications:

• **PROJECT DESCRIPTION**

PCCP: Length: 850 meters; Width: 5 meters; Thickness: 0.20 meter
Shoulders: 1.5 meters both sides
RCPC: 28 in.m 36" diameter and 7 in.m 1.0m diameter

• **SCOPE OF WORK**


Road Concreting
Item 103 (6) - Structure Excavation: 67.20 cu. m.
(pipe culvert and drain excavation)
Item 104 - Embankment 900 cu.m.
Item 105 - Subgrade Preparation: 6,800 sqm.
Item 201 - Base Course Preparation: 1,656.00 cu.m.
Item 311 - Portland Cement Concrete Pavement: 4,250.00 sqm.
Item 500 (1a) - Pipe Culverts, 910mm dia: 28in.m
(36"Ø) and (1.0m Ø)
SPL -1 - Billboard: 1.00 lot

PROJECT DURATION: 128 Calendar Days

PROJECT SITE: Brgy. Minapan, Tulunan, North Cotabato

Done this ____ day of JAN 30 2017 at Koronadal City, Philippines.

Very truly yours,


ENGR. MILAGROS CAPAO-AN CASIS
Head of the Procuring Entity
Regional Executive Director

Acknowledge Receipt:

PRECIOUS CAPAO-AN DARDO

Signature Over Print Name

Date 1-30-2017

Prepared by 

ANNABELLE V. OMICTIN
Vice Chairman - BAC Secretariat

Notice to Proceed - Concreting of Minapan FMR Phase 1
Php7,719,477.44
Page 1 of 1