



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
Regional Field Office XII

Office of the Bids and Awards Committee (BAC)
Regional Government Center, Carpenter Hill,
Koronadal City, South Cotabato
Telefax No. (083) 228-3411

NOTICE TO PROCEED

EVELYN C. TAMONI

President

Isulan ECT Construction & General Merchandise, Inc.

National Highway, Brgy. Laguinding

Esperanza, Sultan Kudarat

Dear Ms. Tamoni,

Having entered into a contract with the Department of Agriculture, RFO 12, Koronadal City, please be advised that you may now proceed with the project entitled **Construction of 2 units Rubber Sheet Processing Facility** in the amount of **Two Million Five Hundred Thousand Pesos (Php2,500,000.00)** with **ITB Reference No. 4523476**, subject to the terms and conditions of the contract agreement specifically the provision on "LIQUIDATED DAMAGES" (LD) as stipulated under RA 9184 with the following scope of works:

Project of Description: Dimension: W = 9.00m, L = 20.00m, H = 6.00m (NGL to Roof Apex Line), Total Floor Area = 255.36 sq.m. (Including 2 side pathways)

Scope of Work:

Item 103	- Earthworks (Structural Excavation and Backfill)	: 1.00 L.S.
Item 900 (1)	Reinforced Concrete:	
	a. Footing	: 6.30 cu.m.
	b. Column	: 9.64 cu.m.
	c. Footing Tie Beam	: 3.48 cu.m.
	d. Wall Footing	: 1.65 cu.m.
	e. Concrete Flooring	: 18.00 cu.m.
	f. 2 Side Pathway Flooring	: 7.54 cu.m.
	g. Wall Stiffener	: 1.02 cu.m.
	h. Concrete Coagulation	: 1.52 cu.m.
	i. Platform of Water Tank	: 4.50 cu.m.
	j. Platform of Motor Engine	: 0.70 cu.m.
Item 901 (2)	- Masonry Works (Include wall finish)	
	a. Wall	: 51.00 sq.m.
	b. Finishing Touch	: 2.55 cu.m.
Item 1002 (1)	- Plumbing	
	a. Sanitary & Drainage Line	: 1.00 lot
	b. Water Line	: 1.00 lot
	c. Septic & Drainage	: 10.50 sq.m.
Item 1003 (a)	- Carpentry Works	
	a. Ceiling and Joist	: 18.00 sq.m.
	b. Wooden Door and Jamb	: 2.00 lot
	c. Forms and Support	: 1.00 lot
	d. Air Hanger Part and Works	: 1.00 lot
Item 1004	- Hardware	: 1.00 lot
Item 1013 (2)	- Roofing Corrugated Sheet (Ga. 26)	: 209.76 sq.m.

Item 1018 (a)	- Tile Works	: 1.00 lot
Item 411	- Painting Works (All Types)	: 1.00 lot
SPL 1	- Tinsmithry Works	
	a. Trusses	: 1.00 lot
	b. Purlins	: 1.00 lot
	c. Fascia & Steel Flashing	: 1.00 lot
	d. Steel Strut	: 1.00 lot
	e. Steel Railing Guide	: 1.00 lot
	f. Windows	: 4.00 lot
	g. Canopy	: 1.00 lot
SPL 2	- Electrical Works	: 1.00 lot


Project duration: Three Hundred (300) Calendar Days


Project location:

1. LGU-Kidapawan City, North Cotabato
2. LGU-Pigcawayan, North Cotabato

Done this ____ day of JUL 24 2017 2017 at Koronadal City, Philippines.

Very truly yours,


MILAGROS CAPAO-AN CASIS, CE
 Head of the Procuring Entity
 Regional Executive Director

Acknowledged/Receipt:

LUIBETH DUMOL
 Signature/Over Printed Name
 Date July 24, 2017