

PURCHASE ORDER

Department of Agriculture

Region XII, Koronadal City

Supplier **NR Eustaquilo Enterprises, Inc.**P.O. No. 2022Address **C.M. Recto St., Brgy. 34-D, Poblacion District, Davao City**Date: 10-30-17Mode of Procurement: Public Bidding

Gentlemen:

Please furnish this office the following articles subject to the terms and conditions contained herewith:

Place of Delivery: DA - RFO XII, Carpenter Hills, Koronadal City Delivery Term: Forty-Five (45) Calendar Days

Date of Delivery: _____ Payment Term: _____

Item No.	Unit	Qty	Description	Unit Cost (P)	Amount
			Supply and Delivery of Surveying Instrument		PHP 988,000.00
1	unit	2	A. STONEX R2W Plus 2" R500 TOTAL STATION (Color Touchscreen) (Premium Quality European Brand)	480,000.00	PHP 960,000.00
			Specifications:		
			- 500 Relectorless range, 2 accuracy. Double Position Coordinate .system (Nothing, Easting/ Latitude, Longitude/ Geodetic Lot)		
			- Display: Two sides, 3.55" Color TFTLCD (320x240 pixel), touchscreen		
			- Windows CE operating system supports a full alphanumeric pop up keyboard helping users to enter quickly and accurately		
			- Magnification: 30 x 80 x 36 with optional eyepiece		
			- Objective aperture: 45mm		
			- Field view: 1°30"		
			- Resolving power: 3"		
			- Minimum focusing distance: 1.0m		
			- Laser pointer: Coaxial Red Light		
			- System: Electronic dual-axis compensator, working range/accuracy: ±3.0'/1"		
			- 2 hot swappable internal rechargeable li-ion batteries: 3400mAh Li-on battery rechargeable. Output Voltage: 7.4V; Operating Period with measurement with continuous angle measurement: 12 hours; Operating Period with measurement every 30 seconds: approx.: 9 hours (>1000measurements); Charger: 110V/240V; Charging Time: (at +20°C): approx.. 4 hours		
			- Dual slot battery charger with AC adapter		
			- Built-in scientific calculator		
			- Endless tangent screw		
			- Advance Cogo, Advance 3D road lay-out		
			- Cable - free Bluetooth effective distance: 10m, transfer data from total station and to GPS controller		
			- LumiGuide for stakeout assistance		
			Sub-Total		PHP960,000.00