



**Republic of the Philippines**  
**DEPARTMENT OF AGRICULTURE**  
**Regional Field Office XII**  
**Koronadal City**  
**BAC Secretariat Office Tel./Fax No. 0835200564**

April 26, 2013

**INVITATION TO BID**

THE DEPARTMENT OF AGRICULTURE, REGION XII, KORONADAL CITY INVITES PROSPECTIVE BIDDERS FOR THE SUPPLY AND DELIVERY OF THE FOLLOWING ITEMS:

**RICE PROGRAM:**

- 1. Construction of 70 units Palay shed                      ABC: P10,500,000.00**

**Specifications:**

**Flooring:**

Dimension: Length= 9m,width=6m  
 Thickness: 4" (.10m)  
 Concrete mixture: Class B (1:2.5.5.5)  
 10mm diameter reinforcing steel bar sp. 0.60m O.C, both ways

**Column:**

0.25mx0.25m concrete column with clear height of 2.80m  
 Concrete mixture; Class A=1:2:4  
 10mm dia., reinforcing steel bar w/ 10mm dia., lateral ties tied with #6 tie wire

**Roofing:**

Roofing sheets shall be made of brand new G.A. #26  
 Corrugated GI sheet  
 Roofing sheets shall be connected to the purlins by using self-tapping roof metal screws of "tekscrew"  
 Trusses shall be made of ¼ thick 11/2" x 11/2" (top-bottom chord)  
 And 3/6" thick 1"x1" angle bar (Web Member)  
 Steel strut- ¼" thick 11/2"x11/2" angle bar w/ 3/16" thick 1"x1" web member

**Locations:**

Sarangani	= 4
Gensan City	= 1
South Cot.	=13
North Cot.	=26
Sultan Kudarat	=25
Cot. City	= 1
Project Completion	=120 days

- 2. Construction of 85 units mini warehouse w/MPDP                      ABC: P59,500,000.00**

**Specifications:**

**Mini-warehouse**

Length = 11m  
 Width = 6m  
 Height = 3.15m  
 Floor thickness= 0.15m(6") reinforced with 10mm 0 RSB sp. @0.60m both ways  
 With DA logo

### **Multi-purpose Drying Pavement**

Area = 420 sq.m.  
Dimensions = length=28m; width= 15m  
Thickness = 0.1m(4 inches)  
Mixing Proportion= 1:2:4 (class A)

#### **Locations:**

Sarangani = 5  
Gensan =1  
Sout Cot. =18  
North Cot. =30  
Sultan Kudarat =30  
Cot. City = 1  
Project Completion =120 days

### **3. 20 UNITS RICE SEED CLEANER ABC: 1,060,000.00**

#### **Specifications:**

ENGINE: Gasoline, air cooled  
6HP Rated power  
Japanese brand or its equivalent  
Brand new

#### **CLEANER:**

-1 to 1.5 tons/hour for initial cleaning after threshing  
-1.5 to 2 tons/hour for final cleaning after drying  
-97% grain purity after two passes  
-Less than 1% cleaning loss  
-With brand new pneumatic tires for towing and transport  
-Can be used to clean inbred and hybrid seeds  
Workmanship should conformed to PAES 204:2000  
With basic tools  
With reflectorized DA Agri Pinoy logo  
With minimum 1 year warranty  
Delivery period: 30 days  
Delivery site: DA-Tupi,Bolol-mala,South Cotabato

### **4. 310 UNITS KNAPSACK SPRAYER ABC:P 930,000.00**

#### **Specifications:**

16 liters  
Stainless steel chamber material  
Delivery period: 30 days  
Delivery site: DA-Tupi,Bolol-mala,South Cotabato

### **CORN PROGRAM**

### **5. ONE(01) UNIT GRAIN SILO (Design and Build Mode) ABC:P2,000,000.00**

#### **Specifications:**

Type: Flat bottom  
Capacity: 200-250 tons  
Materials: galvanized steel plate @ 200 to 275 g/m<sup>2</sup>  
Discharge Option: Drag conveyor single inlet; manual or electrical-slidegates  
Vertical conveyor capacity: 5 to 8 tons/hr.  
Foundation: concrete slab with conical hopper  
Wall Diameter: 6 to 6.41m  
Wall Height: 9 to 9.75m  
Project Completion: 160 days  
Location: Brgy. Sinawal,Gensan City

**Condition: Silo designed to withstand wind gusts to 200km/hr and with additional external wind-bracing available for risk or exposed applications.**

**6. ONE(01) UNIT CASSAVA DRYER CENTER ABC:P3,560,000.00**

**Specifications:**

**Multi-belt dryer for granulated cassava**

- Feed rate 1MT per hour minimum when drying from 65%MC to 13% final MC
- Discharge rate 0.4 MT/hour minimum
- Drying residence time: 2 hours minimum
- Drying temperature: 80 to 100 degree centigrade

**Multi-Fuel Biomass Furnace**

- multi-fuel, corn cobs, rice hull, wood chips, saw dust direct fired
- Capable of heating ambient air to 100 degree centigrade at airflow rate of 40,000 cfm minimum at 1 inch water static pressure

**Electric power transformer**

- 50KVA, 220V, single phase of three phase

**Drying Shed**

- Floor area 9m x 14m= 126 sq. m.
- minimum
- Eave height 7.5m minimum
- Project completion: 160 days
- Location: Tampakan, South Cotabato

**7. 1,000 bags hybrid white corn seeds ABC: P3,000,000.00**

**Specifications:**

- High yielding variety @ 18 kilos/bag
- Drought resistant
- 90% germination rate
- Delivery period 30 days
- Delivery site: DA-RFO 12 Designated stations
- Inscript in a one side of the bag w/ plastic lining the big bold letters  
“AGRI PINOY CORN CALAMITY SEEDS ASSISTANCE PROJECT”

**8. OPV White Corn seeds Registered (1700 bags) ABC: P2,000,000.00**

**Specifications:**

- Registered variety @ 18 kilos/bag
- Drought resistant
- 90% germination rate
- Delivery period: 30 days
- Delivery site: DA-RFO 12 designated stations
- Inscript in a one side of the bag w/plastic lining the big bold letters  
“AGRI PINOY CORN CALAMITY SEEDS ASSISTANCE PROJECT”

**HVCDP PROGRAM**

**9. 3,800 BAGS ORGANIC FERTILIZER ABC: P950,000.00**

**Specifications:**

- 50 kgs/bag
- 50% vermin cast
- Minimum NPK 2-2-2
- Delivery period: 30 days
- Delivery site: Different municipalities of Region XII

**10. 1 UNIT 4WD TRACTOR****ABC: P882,294.30****SPECIFICATIONS:**

Brand new 4WD tractor with canopy

Front weights: 100 kgs

Power take off: 31HP

**ENGINE:**

30-35HP, 3 cylinders, 4 cycle, diesel, water cooled

**IMPLEMENTS(fabricated)**

-3 blades disc plow, 16-18 inches diameter

-Rotavator with 8 blades each for right and left

-Heavy duty trailer, with brand new tires rim size R15

@ least 2 tons capacity

AMTEC tested

Implements workmanship should conform to PAES 104:2000

With basic tools

With reflectorized DA12 Agri pinoy logo

With minimum 1 year warranty

Delivery period: 30 days

Place of delivery: DA Tupi, Bolol-mala, South Cotabato

**11. ASSORTED GARDEN TOOLS (Gulayan sa Paaralan)****Specifications:****ABC**

550 pcs. shovel (heavy duty)	P275,000.00
550 pcs. rake (heavy duty,teeth notwelded)	264,000.00
550 pcs. grab hoe(heavy duty, 3/16 thick)	206,250.00
550 pcs. bolo(heavy duty, 3/16 thick)	206,250.00
550 pcs. hand trowel(heavy duty, rubber handle)	77,000.00
<b>TOTAL</b>	<b>P1,028,500.00</b>

Delivery period: 20 days

Delivery site: APCO office, Gen. Santos City

**FARM TO MARKET ROAD****12. Concreting of Sikitan, Kidapawan City**

Location: Kidapawan City

ABC : P5,000,000.00

**Description:**

Roadway width =4 meters

PCCP Thickness =0.20 meters

Net length =700 meters

Ptoject Completion =120 days

**13. Concreting of BAO FMR,Alamada, Cotabato**

Location: Alamada, Cotabato

ABC : P6,000,000.00

**Description:**

Roadway width =4 meters

PCCP Thickness =0.20 meters

Net length =840 meters PCCP

=245 meters gravelling

Project Completion: =120 days

**14. LABOR AND MATERIALS FOR THE REPAIR OF FARMERS PAVILLION**  
DA-CEMIARC, Amas, Kidapawan City  
**ABC: P623,000.00**

**15. (Tissue Culture Laboratory) Equipment/Apparatus and Reagents**  
**DA-CEMIARC,Balindog,Kidapawan City)**  
Trust Fund  
**ABC: P1,000,000.00**

**PRE-BID CONFERENCE :       MAY 06, 2013 @ 9:00 AM**  
**DA-RFO 12, Zulueta St., Koronadal City**

**OPENING OF SEALED BIDS : MAY 20, 2013 @ 9:00 AM**  
**DA-RFO 12,Zulueta St.,Koronadal City**

**AVAILABILITY OF BID DOCUMENTS :   APRIL 29,2013 TO MAY 17, 2013**  
**8:00AM TO 5:00PM**  
**DA-RFO 12,Koronadal City**

The DA-RFO 12 reserves the right to accept any bid, to annul the bidding process, and to reject all bids at anytime without thereby incurring any liability to the affected bidder or bidders and to accept bids most advantageous to the government.

**ENRIQUETO G. NATIVIDAD**  
**BAC Chairman**