



NOTICE TO PROCEED/DELIVER

THE PROPRIETOR

Freden Construction
Zone 7, Block 8, Brgy. Fatima
General Santos City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting of Lun Masla - Kinam FMR in Malapatan, Sarangani Province** with **ITB Reference No. 3077337** in the amount of **Twenty-Two Million Three Hundred Fifty Thousand Nine Hundred Ninety-Nine Pesos and 80/100 (Php22,350,999.80)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following Project Description and Scope of Works, to wit:


Project Description : Concreting of 2.50 km road at 5.0 l.m. width and 20 cm thickness with programmed gravel shouldering on both sides, Installation of 19l.m. 910mm dia. RCPC Cross Drainage Structure with Headwall, and construction of 568l.m. CHB Lined Canal


Scope of Works:

SPL 1	- Project Billboard	: 64 sqft
SPL 2	- CHB Lined Canal	: 568 l.m.
Item 100(3)	- Individual Removal of Trees Small	: 59 pcs
Item 101	- Removal of Structures and Obstructions (headwall)	
Removal of Existing Concrete Bench, Signage & Headwall		: 12 pcs
Removal of Existing RCPC		: 8.00 l.m.
Removal of Existing PCCP		: 138.80 m ²
Item 102(2)	- Surplus Common Excavation.	: 11,679.18m ³
Item 103(6)	- Pipe Culvert and Drain Excavation	: 596.50 m ³
Item 104	- Embankment	: 1,190.04 m ³
Item 105	- Sub-grade Preparation	: 20,000 m ²
Item 201	- Aggregate Base Course	: 5,797.98m ³
Item 311	- Portland Cement Concrete Pavement	: 12,500 m ²
Item 407	- Concrete Structures (Headwall)	: 19.23 m ³
Item 500(a)	- RC Pipe Culvert, 910mm dia.	: 19l.m.

Project Duration : 220 Calendar Days


Very truly yours,


AMALIA J. DATUKAN, MBA
Regional Executive Director

Conformed: 

RICHARD H. SULUS
Print Name and Signature
Date : JUNE 28, 2015

Prepared by:


MONINA M. SALENDAB
Head, BAC Secretariat