



NOTICE TO PROCEED

The Proprietor
ILBI Construction Supply and Services
Reyes Subdivision, Koronadal City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, RFO 12, Koronadal City, you are hereby authorized to proceed with the **Construction of Balite Diversion Dam and Concreting of Canal, Magpet, Cotabato** with ITB Reference No. 2844477 in the amount of **Six million Nine Hundred Thirty-Six Thousand Sixty-Six Pesos and 55/100 (Php6,936,066.55)** which shall be completed within **One Hundred Eighty (180) calendar days**, subject to the terms and conditions of the contract agreement with the following specifications and Scope of Works, to wit:

Item No.	Description	Unit	Quantity
I.	DAM WORKS:		
1.1	Clearing and Grubbing	LS	
1.2	Rock Excavation	cu.m.	142.8
1.3	Common Excavation	cu.m	255.8
1.4	Backfill	cu.m	245
1.5	Class "A" Concrete	cu.m.	151.6
1.6	Reinforcing Steel Bar	kg.	7,726.3
1.7	Grouted Riprap	cu.m.	104.3
1.8	Gravel Blanket	cu.m.	52.2
1.9	Rubble Masonry	cu.m	123.5
1.10	Flashboard	assy	2.00
1.11	Trash Rack	assy	1.00
1.12	2" dia. PVC Pipe (Weep Hole)	Lin.m.	5.00
II	Outlet Works		
II.1	Common Excavation	cu.m.	83.7
II.2	Structural backfill	cu.m.	60.87
II.3	Class "A" Concrete	cu.m.	11.18
II.4	Reinforcing Steel Bar	kg	503.10
II.5	Rectangular Sliding Steel Gate	assy.	1.00
II.6	Grouted riprap	cu.m.	2.70
II.7	Gravel Blanket	cu.m	1.35
III.	Irrigation canal (795 meters)		
III.1	Excavation	cu.m.	979.40
III.2	Backfill	cu.m.	859.20
III.3	Concrete Class "A"	cu.m	155.70
III.4	Reinforcing Steel Bar	kg.	6,695.1
III.5	Gravel Blanket	cu.m	47.70
III.6	Flashboard	assy	4.000

IV

Concrete Signage with DA logo and Markings

IV.1	CHB, 4" x 8" x 16"	pcs.	124.00
IV.2	Cement	bags	16.00
IV.3	Sand	cu.m	1.00
IV.4	Gravel	cu.m.	2.00
IV.5	10mm dia. X 6m RSB	pcs.	11.00
IV.6	Tie wire	kg.	1.00
IV.7	Form Lumber	bdft.	20.00
IV.8	Plywood, 1/4" x 4' x 8'	pcs.	1.00
IV.9	CW Nails (asstd)	kg	5.00
IV.10	Engraved Printing with DA logo markings	lot	1.00

V.

Flume (205 meters)

V.1	Excavation	cu.m	105.40
V.2	Structural backfill	cu.m	95.60
V.3	Class "A" concrete	cu.m	64.70
V.4	Reinforcing Steel Bar	kg.	3,107.40
V.5	Form lumber/scaffolding	bdft	200.00

Project Duration: 180 calendar days

Acknowledged Receipt:

FETRONILLO H. DANUSONG

Print Name and Signature

Date *Jan. 27, 2015*

Very truly yours,

Amalia J. Datukan
AMALIA J. DATUKAN, MBA,
 Regional Executive Director