



Republic of the Philippines

**DEPARTMENT OF AGRICULTURE**

REGIONAL FIELD OFFICE No. 12  
CSA-1 BUILDING, ZULUETA STREET  
KORONADAL CITY  
TEL No./FAX No. (083)-520-0564

**NOTICE TO PROCEED/DELIVER**

**THE PROPRIETOR**

Palmares General Merchandise  
#5 Public Market Bldg., Magsaysay Avenue  
Tacurong City, Sultan Kudarat

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting/Upgrading of San Felipe - Tinongcop FMR in Brgy. San Felipe, Tantaran, South Cotabato** with ITB Reference No. 2728886 in the amount of **Seventeen Million Seventeen Thousand Nine Hundred Seventy-Two Pesos and 23/100 (Php17,017,972.23)**, subject to the terms and conditions of the contract, with the following Project Description and Scope of Works, to wit:

**Project Description** : Concreting of 2.10 km road (940 l.m. at 5.0 l.m. width and 1,160 l.m. at 6.10 l.m. width) with 20 cm thickness, 1.5 l.m. gravel shoulder on both sides, construction of 660 l.m. Grouted Riprap Structure

**Scope of Works:**


Item 102	- Roadway Excavation	: 3,335.10 m <sup>3</sup>
Item 104	- Embankment	: 2,982.96 m <sup>3</sup>
Item 103(1)	- Structure Excavation	: 660 m <sup>3</sup>
Item 505	- Grouted Riprap	: 561.70 m <sup>3</sup>
Item 103(3)	- Foundation Backfill	: 396 m <sup>3</sup>
Item 105(1)	- Subgrade preparation	: 20,640 m <sup>2</sup>
Item 201	- Aggregate Base Course (base and shoulder)	: 5,211.20 m <sup>3</sup>
Item 311(1)	- Portland Cement Concrete Pavement	: 11,776 m <sup>2</sup>
SPCL "A"	- Informative sign board	: 1 lump sum

Project Duration : 210 Calendar Days

Very truly yours,

  
AMALIA J. DATUKAN, MBA  
Regional Executive Director

Conformed:

  
Print Name and Signature

Date : 10/7/14