



February 19, 2014

NOTICE TO PROCEED

The Proprietor  
RDEN Construction and Supply  
Quezon Avenue, Libungan, North Cotabato

Sir:

Having entered into a contract with the Department of Agriculture, RFO 12, Koronadal City, you are hereby authorized to proceed with the **Construction of Simsiman Small Water Impounding Project (SWIP)** located at **Simsiman, Pigcawayan, Cotabato** in the amount of **Two Million Nine Hundred Ninety-Two Thousand Six Hundred Ninety-Six Pesos and 06/100 (Php2,992,696.06)**, subject to the terms and conditions of the contract agreement with the following Scope of Works:

Item No.	Description	Unit	Quantity
DAM WORKS:			
I.			
1.1	CLEARING AND GRUBBING	L.S	L.S
1.2	EXCAVATION		
	1.2a Stripping	cu.m	259.20
	1.2b Core Trench	cu.m	396.00
1.3	EMBANKMENT FILL		
	1.3a Side borrow	cu.m	1,580.00
	1.3b Hauled materials	cu.m	296.25
	1.3c From core Trench and Spillway Excavation	cu.m	98.75
1.4	Rock Toe Drain	cu.m	45.35
1.5	Fine Sand Transition	cu.m	20.41
1.6	Gravel and Sand Transition	cu.m	11.34
1.7	HAndlaid Riprap	cu.m	127.91
1.8	Gravel Blanket	cu.m	63.96
1.9	Sprigging and Sodding	cu.m	660.00
1.10	Gravel Surfacing	cu.m	198.00
II.	SPILLWAY WORKS		
II.1	Excavation	cu.m	122.50
II.2	Structural Backfill	cu.m	105.65
II.3	Concrete Class "A"	cu.m	27.98
II.4	Reinforcing Steel Bar	kg	1,343.18
II.5	Grouted Riprap	cu.m	14.95
II.6	Gravel Blanket	cu.m	7.475



III. OUTLET WORKS


III.1	Excavation	cu.m	75.00
III.2	Structural Backfill	cu.m	60.84
III.3	Concrete Class "A"	cu.m	11.75
III.4	Reinforcing Steel Bar	kg.	505.25
III.5	Gate Valve: Cast Iron Flange Type 8" dia	pc.	1.00
III.6	Polyethylene Pipe(PE Pipe,SDR9	pcs.	4.00
III.7	Fish screen/Trashrack	assy.	1.00


IV IRRIGATION WORKS

IV.1	Excavation	cu.m	257.03
IV.2	Structural Backfill	cu.m	384.00
IV.3	Concrete Class "A"	cu.m	80.07
IV.4	Reinforcing Steel Bar	kg.	3,469.84
IV.5	Leveling Course	cu.m	55.13

**Project Completion: 90 calendar days**

Very truly yours,

  
Acknowledged Receipt:  
RUPERTO A. DENOLAN  
Print Name & Signature  
Date FEBRUARY 19, 2014

  
AMALIA J. DATUKAN, MBA  
Regional Executive Director