



### NOTICE TO PROCEED

**The Proprietor**  
**Amplex Construction and Supplies**  
**Purok 2A Lower Tupi, Poblacion**  
**Tupi, South Cotabato**

Sir/Madam:

Having entered into a contract with the Department of Agriculture, RFO 12, Koronadal City, you are hereby authorized to proceed with the **Construction of Upland Multi-Purpose Shed at Tupi Seed Farm, Bololmala, Tupi, South Cotabato** with ITB Reference No. 2871546 in the amount of **One Million Nine Hundred Three Thousand Seven Hundred Twenty-Seven Pesos and 98/100 (Php1,903,727.98)** which shall be completed within **Forty-Five (45) calendar days** subject to the terms and conditions of the contract agreement with the following specifications and Scope of Works, to wit:

Item No.	Description	Unit	Quantity
<b>I</b>	<b>Concrete Works</b>		
<b>I.a</b>	<b>Footings:</b>		
	Cement	bags	50
	Washed sand	cu.m	3
	Gravel	cu.m	4
	16mm dia x 6.00m RSB	pcs.	24
	#16 tie wire	kgs.	2
<b>I.b</b>	<b>Column:</b>		
	Cement	bags	55
	Washed sand	cu.m	3
	Gravel	cu.m	5
	16mm dia. X 6.00m RSB	pcs.	30
	10mm dia x 6.00m RSB	pcs.	60
	#16 Tie wire	kgs	3
<b>I.c</b>	<b>Pavement:</b>		
	Cement	bags	583
	Washed sand	cu.m	47
	Gravel	cu.m	37
	12mm dia. X 6.00m RSB	pcs.	238
	#16 Tie wire	kgs	2
<b>II</b>	<b>Tinsmithry Works</b>		
<b>II.a</b>	<b>Truss:</b>		
	¼" thk x 2" x 2" x 20' angle bar	pcs.	334
<b>II.b</b>	<b>Steel Strut:</b>		
	¼" thk x 2" x 2" x 20' angle bar	pcs.	50

Item No.	Description	Unit	Quantity
II.c	Base plate: 9mm thk, 40cm x 50cm steel plate	pcs.	12
II.d	Cleaf: ¼" thk x 1 ½" x 1 ½" x 20' angle bar	pcs.	12
II.e	Cee purlins: 1.20mm x 50mm x 150mm C-purlins	pcs.	85
II.f	Anchor bolt: 19mm dia x 350mm bolt w/ knot and washer	pcs.	36
<b>III.a</b>	<b>Roofing and Accessories:</b>		
	Cor galvalum sht, Ga24,12'- color baguio green	sht	165
	4.5mm dia x 50mm tekscrew	pcs.	3,965
	0.40mm thk pre-painted galvalum-ridge roll	sht	9
	Flat bar metal plate, 10mm x 100mm x 400mm	pcs.	6
	20mm dia x 50mm bolt with knot and washer	pcs.	9
	Sag rod, 12mm dia pln. Round bar, 6m	pcs.	17
	Cross bracing bar, 16mm diapl round bar, 6m	pcs.	27
	16mm dia x 300mm turn buckle	pcs.	40
	Vulca seal (roof and PVC sealant)	gal	1
<b>IV.a</b>	<b>Provision of gutter with downspout and flashing:</b>		
	GI plain sheet, Ga26(pre fab) gutter	sht	30
	GI plain sheet, Ga26 3' x 8'- flashing	sht	18
	Downspout, 3" dia x 20'-PVC pipe, sch 40 orange	pcs.	24.0
	Angular bar, 1/8" x 1 ½" x 20'	pcs.	25
	Flat bar, 1/8" x 1 ½" x 20	pcs.	18
	1/8" x ¼" - rivet (50pcs/box	box	20
<b>V</b>	<b>Hardware:</b>		
	Welding rod	kg	50
	4" CW nail	kg	25
	3" CW nail	kg	10
	2" CW nail	kg	5
	1 ½" CW nail	kg	2
<b>VI</b>	<b>Form Lumber</b>		
	¼" x 4" x 8" ordinary plywood	pcs.	12
	2x2x12 good lumber	pcs.	46
	2x3x12 coco lumber	pcs.	45
	2x4x12 coco lumber	pcs.	45
	Bamboo pole at 30ft long	pcs	11
<b>VII</b>	<b>Painting works:</b>		
	Red oxide(epoxy primer)	gal	15
	Roof guard paint	gal	30
	Neutralizer	gal	15
	Steel paint brush 4"	pc.	10
<b>VIII</b>	<b>Electrical installation and accessories</b>	LS	
	<b>Project Duration: 45 calendar days</b>		

Acknowledged Receipt:

Print Name and Signature

Date 1-19-15

Very truly yours,

*Amalia J. Datukan*  
**AMALIA J. DATUKAN, MBA**  
 Regional Executive Director