



### NOTICE TO PROCEED

The Proprietor  
Triple Z Merchandising & Electrical Supply  
Paparon Compound, Aparente Street  
Brgy., City Heights, General Santos City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, RFO 12, Koronadal City, you are hereby authorized to proceed with the **Construction of 23 Units Palay Shed (Cluster A)** with ITB Reference No. 2784325 in the amount of **Three Million Seven Hundred Eighteen Thousand Nine Hundred ninety-Eight Pesos and 75/100 (Php3,718,998.75)** which shall be completed within **one hundred thirty (130) calendar days**, subject to the terms and conditions of the contract agreement with the following specifications and Scope of Works, to wit:

#### Description

##### A. Flooring

- Dimension: length- 9m; width- 6m
- Thickness : 4" (.10m)
- Concrete Mixture : Class B (1:2.5.5.5)
- 10mm diameter reinforcing steel bar sp. 0.60m 0.c both ways


##### B. Column

- 0.25m x0.25m concrete column with clear height of 2.80m
- Concrete mixture : Class A (1:2;4)
- 10mm dia. Reinforcing steel bar with 10mm dia. Lateral ties tied with #6 tie wire


##### C. Roofing

- Sheets shall be made of brand new G.A. # 26
- Corrugated GI sheet
- Roofing sheets shall be connected to the purlins by using self-tapping roof metal screw of "tekscrew"
- Trusses shall be made of ¼ thick 1 ½" x 1 ½" (top bottom chord) and 3/6" thick 1" x 1" angle bar 9web member)
- Steel strut- ¼' thick 1 ½" x 1 ½" angle bar with 3/6" thick 1" x 1" angle bar(web member
- Roofing painted with " Mula s Tao, Para sa Tao" and DA Agri Pinoy logo
- With 3x6m marker and engrave in wall fronting to roadside (content of marker includes: DA and Agri Pinoy logo, project title and project recipient)

Very truly yours,

  
AMALIA J. DATUKAN, MBA  
Regional Executive Director

Acknowledged Receipt:

  
Print Name & Signature  
Date JAN 6 2011