

### NOTICE TO PROCEED

The Proprietor  
Rely Construction and Supply  
Km. 7, Tigatto Road, Buhangin, Davao City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, RFO 12, Koronadal City, you are hereby authorized to proceed with the **Construction of 47 Units Palay Shed (Cluster B)** with ITB Reference No. 27 84325 in the amount of **Seven Million Seven hundred Forty-Four Thousand Nine Hundred Twenty-Six Pesos and 73/100 (Php7,744,926.73)** which shall be completed within **one hundred thirty (130) calendar days**, subject to the terms and conditions of the contract agreement with the following specifications and Scope of Works, to wit:

#### Description

##### A. Flooring

- Dimension: length- 9m; width- 6m
- Thickness : 4" (.10m)
- Concrete Mixture : Class B (1:2.5.5.5)
- 10mm diameter reinforcing steel bar sp. 0.60m 0.c both ways

##### B. Column


- 0.25m x0.25m concrete column with clear height of 2.80m
- Concrete mixture : Class A (1:2;4)
- 10mm dia. Reinforcing steel bar with 10mm dia. Lateral ties tied with #6 tie wire

##### C. Roofing


- Sheets shall be made of brand new G.A. # 26
- Corrugated GI sheet
- Roofing sheets shall be connected to the purlins by using self-tapping roof metal screw of "tekscrew"
- Trusses shall be made of ¼ thick 1 ½" x 1 ½" (top bottom chord) and 3/6" thick 1" x 1" angle bar 9web member)
- Steel strut- ¼' thick 1 ½" x 1 ½" angle bar with 3/6" thick 1" x 1" angle bar(web member)
- Roofing painted with " Mula s Tao, Para sa Tao" and DA Agri Pinoy logo
- With 3x6m marker and engrave in wall fronting to roadside (content of marker includes: DA and Agri Pinoy logo, project title and project recipient)

##### D. Construction Period: 130 calendar days

Very truly yours,

  
AMALIA J. DATUKAN, MBA  
Regional Executive Director

Acknowledged Receipt:

  
RENATO P. CASTAÑEDA  
Print Name & Signature  
Date DEC. 5 2014