



Republic of the Philippines  
**DEPARTMENT OF AGRICULTURE**  
 Regional Field Office XII  
 Brgy. Carpenter Hill, General Santos Drive  
 Koronadal City  
 Tel. No./Fax No. : 083-520-0460

**NOTICE TO PROCEED/DELIVER**

**THE PROPRIETOR**  
**Freden Construction**  
 Zone 7, Blk. 8, Brgy. Fatima  
 General Santos City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting of New Dumangas - Laconon FMR in Brgy. New Dumangas, T'boli, South Cotabato with Reference No. 3661467** in the amount of **Twenty-One Million One Hundred Eighty-Three Thousand One Hundred Seventy-Four Pesos and 63/100 Only (Php21,183,174.63)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following project Description and Scope of Works, to wit:

**Project Description** : Concreting of 1,850 l.m. road at 6.70 l.m. width and 20cm thickness with road shouldering on both sides, Construction of RCPC cross drainage structures, slope protection structure and 1 unit 1.5m x 1.5m x 8.0m box culvert

**Scope of Works:**  
**PCCP**

- SPCL "A" - Information Signboard : 1 l.s.
- Item 100(2) - Clearing & Grubbing : 1 l.s.
- Item 102(2) - Surplus Common Excavation : 14,277.55 m<sup>3</sup>
- Item 104 (1) - Embankment : 4,741.90 m<sup>3</sup>
- Item 105(1) - Sub Grade Preparation : 18,500 m<sup>2</sup>
- Item 201 - Aggregate Base Course (Base & Shoulder) : 5,328 m<sup>3</sup>
- Item 311 - Portland Cement Concrete Pavement : 12,395 m<sup>2</sup>

**PIPE CULVERT & LINED CANAL.**

- Item 101(1) - Removal of structures and Obstruction : 1 l.s.
- Item 103(6) - Structure Excavation : 214 m<sup>3</sup>
- Item 500(3a) - RCPC 910mm dia : 13 l.m.
- Item 506 - Stone Masonry (Line Canal & Headwall) : 172.73 m<sup>3</sup>
- Item 103(4) - Back Fill : 107 m<sup>3</sup>
- 1.50m x 1.50m x 8.0m box culvert (normal)
- Item 100(1) - Clearing & Grubbing : 1 l.s.
- Item 103 - Structure Excavation : 37.80 m<sup>3</sup>
- SPCL "B" - Detour Road : 1 l.s.
- Item 405(b) - Structural Concrete Class "B" : 2.28 m<sup>3</sup>
- Item 404 - Reinforcing Steel : 3,272.85 kg
- Item 405(a) - Structural Concrete Class "A" : 33.99 m<sup>3</sup>
- Item 103(3) - Foundation Fill : 15 m<sup>3</sup>

**SLOPE PROTECTION**


Item 505(1) - Grouted Riprap Class "A" : 107 m<sup>3</sup>  
Item 103(1) - Structure Excavation : 60 m<sup>3</sup>  
Item 103(3) - Foundation Fill : 49.40 m<sup>3</sup>

Project Duration : 211 calendar days  
Location : Brgy. New Dumangas, T'boli, SouthCotabato


Donethis \_\_\_\_ day of MAR 21 2016, 2016 at Koronadal City, Philippines.

Very truly yours,

  
AMALIA J. DATUKAN, MBA  
Regional Executive Director

Conformed:  
  
FREDDIE M. LAPADA  
Printed Name and Signature  
Date : 3-21-16

Prepared by:

  
MONINA M. SALENDAB  
Head, BAC Secretariat