



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
 Regional Field Office XII
 Regional Center, Brgy. Carpenter Hill
 Koronadal City
 Tel. No./Fax No. : 083-228-3413 / 228-3411

NOTICE TO PROCEED/DELIVER

THE PROPRIETOR
Minrock Multi-Builders
 H.K. Doton Streets
 Cotabato City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting of Chua - Mantisao FMR Phase II in Brgy. Chua, Bagumbayan, Sultan Kudarat with Reference No. 3824347** in the amount of **Sixteen Million Nine Hundred Eighty-Four Thousand One Hundred Ninety-Seven Pesos and 43/100 Only (Php16,984,197.43)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following project Description and Scope of Works, to wit:

Project Description : Concreting of 1.10 km road at 5.0 l.m. width and 20cm thickness with 1.0 l.m.road shouldering on both sides, Construction of Slope Protection and Retaining Wall Structures, RCP Cross Drainage Structures with headwall, chute, catch basins and construction of canal lining

Scope of Works:


Item 100	- Clearing &Grubbing	:8,800m ²
Item 101(2)a	- Removal of RCPC and Storm Drain (24" dia) :	3.00 l.m.
Item 101(2)e	- Removal of RCPC and Storm Drain (48" dia) :	8.00 l.m.
Item 102 (1)	- Roadway Excavation (unsuitable)	: 5,459.60 m ³
Item 103(1)a	- Structure Excavation (common soil)	: 1,899.34 m ³
Item 103(1)c	- Structure Excavation (Solid Rock)	: 472.80 m ³
Item 105	-Sub Grade Preparation	: 8,800 m ²
Item 201	- Aggregate Base Course	: 2,723 m ³
Item 311	- Portland Cement Concrete Pavement :	5,500 m ²
Item 500(1)c	- RCPC 910mm" dia	: 10 l.m.
Item 500(1)e	- RCPC 1220mm" dia	: 56 l.m.
Item 505(5)	- Grouted Riprap Class"A"	: 48.91 m ³
SPL1	- Canal Lining	: 106.56 m ³
SPL2	- Retaining Wall	: 62.72 m ³
SPL3	- Headwall	: 17.86 m ³
SPL4	- Wingwall& Catch Basin	: 27.66 m ³
SPL5	- Chute and Apron	* : 36.64 m ³
SPL6	- Information Signage	: 5.00 units


Project Duration : 275 Calendar Days
 Location : Brgy. Chua, Bagumbayan, Sultan Kudarat

Done this 26th day of August, 2016 at Koronadal City, Philippines.

Very truly yours,


CARLENE S. COLLADO, CPA
 OIC-Regional Executive Director

Conformed: 
 Printed Name and Signature
 Date : 8/26/16

Prepared by:

MONINA M. SALENDAB
 Head, BAC Secretariat