



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
 Regional Field Office XII
 Brgy. Carpenter Hill, General Santos Drive
 Koronadal City
 Tel. No./Fax No. : 083-520-0460

NOTICE TO PROCEED/DELIVER

THE PROPRIETOR
Freden Construction
 Zone 7, Blk. 8, Brgy. Fatima
 General Santos City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting of Lun Masla - Kinam FMR Phase II in Brgy. Lun Masla/Kinam, Malapatan, Sarangani Province with Reference No. 3618639** in the amount of **Twenty-Five Million Six Hundred Eighty-Four Thousand Five Hundred Ninety-Seven Pesos and 70/100 (Php25,684,597.70)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following project Description and Scope of Works, to wit:

Project Description : Concreting of 1,703.10 l.m. Concrete Road at 5.0 l.m. width and 20cm thickness with programmed road shouldering on both sides, Construction 3mx3mx12m Double Barrel Box Culvert, RCPC Cross Drainage Structures, 2,886 l.m. concrete lined canal and 36 l.m. Guardrail

Scope of Works:

- SPL 1 - Mobilization/Demobilization : 1 l.s.
- SPL 2 - Project Billboard : 5.95 m²
- SPL 3 - Concrete Lined Canal : 2,886 l.m.
- SPL 4 - Construction of 1 unit Top stand : 1 unit
- Item 100(1) - Clearing and Grubbing : 1.71 ha
- Item 100(3) - Individual Removal of Trees, Small : 53 each
- Removal of Structures and Obstructions
- Item 101(4a) - Removal of Existing RCPC : 7l.m.
- Item 101(2b) - Removal of Existing Topstand : 1l.m
- Item 102(2) - Surplus CommonExcavation : 54,221.43 m³
- Item 102(3) - Surplus RockExcavation : 7,884.60 m³
- Item 101(1) - Structure Excavation (Guardrails) : 3.85 m³
- Item 103(3) - Foundation Fill (RCPC) : 95.68 m³
- Item 103(6) - Pipe Culvert and Drain Excavation : 1,015.72 m³
- Item 104(1) - Embankment : 361.83 m³
- Item 105(1) - Sub Grade Preparation : 13,879.67 m²
- Item 201 - Aggregate Base Course : 3,796.44 m³
- Item 311(1) - Portland Cement Concrete Pavement : 8,515.50 m²
- Item 404 (a) - Reinforcing Steel (Headwall, Catch Basin, Chute) : 699.36 kg.
- Item 405(1a) - Structural Concrete Class "A" (Headwall, Catch Basin, Chute) : 30.33 m³
- Item 500(1) - Pipe Culvert & Storm Drains 910mm Ø : 50l.m.
- Item 404(b) - Reinforcing Steel (Barrel, Barrel Edge, wingwall/apron & Cut off wall) : 9,369.68 kg
- Item 405(1b) - Structural Concrete Class "A" (Barrel, Barrel Edge, wingwall/apron & Cut off wall) : 131.30 m³
- Item 407(1) - Lean Concrete : 12 m³

Amf


f

Item 506 - Stone Masonry : 72.36 m³
Item 603 (3a) - Metal Guardrails (Metal Beam) including post : 36 m³
Item 603 (3b) - Guardrail (End Piece) : 4 each


Project duration : 252 calendar days
Location : Barangay LunMasla/Kinam, Malapatan, Sarangani

Done this ____ day of MAR 21 2016, 2016 at Koronadal City, Philippines.


Very truly yours,


AMALIA J. DATUKAN, MBA.
Regional Executive Director


Conformed:


FREDDIE M. LAPADA
Printed Name and Signature
Date: 3-21-16

Prepared by:


MONINA M. SALENDAB
Head, BAC Secretariat