



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
 Regional Field Office XII
 Regional Center, Brgy. Carpenter Hill
 Koronadal City
 Tel. No./Fax No. : 083-228-3413/228-3411

NOTICE TO PROCEED/DELIVER

THE PROPRIETOR

Pase Construction
 Ground Floor, Lax Hotel
 Corner Rizal St., Extension Paredes St.
 Koronadal City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting of National Highway - Acmonan FMR in Brgy. Acmonan, Tupi, South Cotabato with Reference No. 3824337** in the amount of **Nineteen Million Three Hundred Forty-Seven Thousand Two Hundred Forty-Nine Pesos and 74/100 Only (Php19,347,249.74)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following project Description and Scope of Works, to wit:

Project Description : Concreting of 1.49175 km road at 6.70 l.m. width and 20cm thickness with 1.50 l.m. road shouldering on both sides, construction of RCP cross drainage structures, 809.33 l.m. CHB Lined Canal and 1-unit 1.60m x 2.0m x 10m Box Culvert

Scope of Works:

| | | |
|---|---|----------------------------|
| SPCL "A" | - Informative Signboard | : 1 set |
| PIPE CULVERT WITH CATCH BASIN | | |
| Item 103(6) | -Structure Excavation | : 221.82m ³ |
| Item 500(1) | - Pipe Culver 910mm diaRCPC | : 34l.m. |
| Item 405(1) | - Structural Concrete Class "A" | : 12.22 m ³ |
| PCCP | | |
| Item 102(2) | - Surplus Excavation | : 2,781.46 m ³ |
| Item 104(1) | - Embankment | : 2,162.68 m ³ |
| Item 105 (1) | -Sub Grade Preparation | : 14,663.98 m ² |
| Item 201 | - Aggregate Base Course (Base & Shoulder) | : 4,353.84 m ³ |
| Item 311(1) | - Portland Cement Concrete Pavement | : 9.994.73 m ² |
| CHB LINED CANAL | | |
| SPCL "B" | - Concrete Demolition | : 0.40 m ³ |
| Item 102(2) | - Common Canal Excavation | : 1,055.12 m ³ |
| Item 103(3) | - Canal Backfill (side borrow) | : 1,002.37l.m. |
| Item 405(1) | - Structural Concrete Class "A" | : 95.71 m ³ |
| SPCL "C" | - chb Lined Canal w/ Plastering | : 809.33 l.m. |
| 1.60m x 2.0m x 10.0m BOX CULVERT | | |
| SPCL "D" | - Detour Road | : 1.0 l.s. |
| Item 103(1) | - Structure excavation | : 54.40 m ³ |
| Item 405(2) | - Structural Lean Concrete (Class "B") | : 1.0m ³ |
| Item 405(1) | - Structural Concrete (Class "A") | : 19.53m ³ |
| Item 404 | - Reinforcing Steel | : 2,333.69 kg |
| Item 103(3) | - Foundation Backfill | : 38.40 m ³ |

Project Duration : 205 Calendar Days
Location : Brgy. Acmonan, Tupi, South Cotabato

Donethis 27th day of June, 2016 at Koronadal City, Philippines.

Very truly yours,

AMALIA J. DATUKAN, MBA.
 Regional Executive Director

Conformed:

CHARLES GREGOR PASCUA

Printed Name and Signature

Date : 16-31-16

Prepared by:

MONINA M. SALENDAB
 Head, BAC Secretariat