



Republic of the Philippines  
**DEPARTMENT OF AGRICULTURE**  
 Regional Field Office XII  
 Regional Center, Brgy. Carpenter Hill  
 Koronadal City  
 Tel. No./Fax No. : 083-228-3413 / 228-3411

**NOTICE TO PROCEED/DELIVER**

**THE PROPRIETOR**

**Cofejok Construction and Supply Corporation**  
 Corner Magbanua & Don Buencamino Streets  
 Kalawag I, Isulan, Sultan Kudarat

- Joint Venture -

**THE PROPRIETOR**

**JV Constech**  
 Poblacion 1, Lebak  
 Sultan Kudarat

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the of **Kalamansig National Road - Obial FMR in Kalamansig, Sultan Kudarat with Reference No. 3824348** in the amount of **Seventeen Million Six Hundred Twenty Thousand Nine Hundred Forty-Seven Pesos and 03/100 Only (Php17,620,947.03)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following project Description and Scope of Works, to wit:

**Project Description** : Concreting of 1,840 l.m. road at 5.0 l.m. width and 20cm thickness with 1.0 l.m. road shouldering on both sides, Construction of RCPC cross Drainage structures with headwall, construction of lined canal with catch basin

**Scope of Works:**

Item 100(1)	- Clearing & Grubbing	: 5,520m <sup>2</sup>
Item 100(2)a	- Individual Removal of Trees	: 16.00 each
Item 101(2)c	- Removal of RCPC 910mm dia	: 12 l.m.
Item 101(3a1)	- Removal of Existing Concrete Pavement	: 160 m <sup>2</sup>
Item 102 (4)	- Roadway Excavation (surplus soft rock)	: 1,467.90 m <sup>3</sup>
Item 104	- Embankment	: 3,899.90m <sup>3</sup>
Item 105	- Sub Grade Preparation	: 12,880 m <sup>2</sup>
Item 201	- Aggregate Base Course	: 3,588 m <sup>3</sup>
Item 311(1)a	- Portland Cement Concrete Pavement (200mmthk)	: 9,200 m <sup>2</sup>
Item 311(1)b	- Portland Cement Concrete Pavement (150mm thk shouldering)	: 205 m <sup>2</sup>
Item 405(a)	- Structural Concrete -Headwall & additional Height of existing canal	: 7.744 m <sup>3</sup>
Item 405(b)	- Structural Concrete -Open Lined Canal & Catch Basin	: 39.893 m <sup>3</sup>
Item 500(1)c	- RCPC 910 mm dia	: 16 l.m.
SPL 1	- Information Signage	: 5 units

Project duration : 220 calendar days  
 Location : Kalamansig, Sultan Kudarat

Done this 27<sup>th</sup> day of June, 2016 at Koronadal City, Philippines.

Very truly yours,

**AMALIA J. DATUKAN, MBA**  
 Regional Executive Director

Conformed:

**Evin J. Calasang**  
 Printed Name and Signature  
 Date: 06/29/16  
 (Cofejok Construction & Supply Corp.)

Conformed:

**Evin J. Calasang**  
 Printed Name and Signature  
 Date: 06/29/16  
 (JV Constech)