



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
 Regional Field Office XII
 Regional Center, Brgy. Carpenter Hill
 Koronadal City
 Tel. No./Fax No. : 083-228-3413 / 228-3411

NOTICE TO PROCEED/DELIVER

THE PROPRIETOR
C.A. Betalac Construction and General Merchandise
 Alunan Highway, Tacurong City
 Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting of Gapok - Baluan FMR Phase II in Brgy. Gapok, Senator Ninoy Aquino, Sultan Kudarat with Reference No. 3824351** in the amount of **Twenty- Eighteen Million Thirty-Four Thousand Six Hundred Twenty-Four Pesos and 06/100 Only (Php18,034,624.06)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following project Description and Scope of Works, to wit:

Project Description : Concreting of 1,840 Lm. road at 5.0 l.m. width and 20cm thickness with 1.0 Lm. road shouldering on both sides, Construction of RCPC cross drainage structures with headwall, construction of lined canal with catch basin

Scope of Works:

Item 100(1)	- Clearing & Grubbing	: 5,100m ²
Item 102 (4)	- Roadway Excavation (surplus common)	: 1,469.60 m ³
Item 103(1)a	- Structure Excavation	: 276 m ³
Item 105	- Sub Grade Preparation	: 11,900 m ²
Item 201	- Aggregate Base Course	: 4,887.50 m ³
Item 311(1)a	- Portland Cement Concrete Pavement (200mmthk)	: 8,500 m ²
Item 311(1)b	- Portland Cement Concrete Pavement (150mm thk shouldering)	: 195m ²
Item 500(1)c	- Pipe Culvert 36" dia	: 8.00 l.m.
Item 500(6)	- Grouted Riprap (Class B)	: 18.00 m ³
SPL1	- Headwall	: 1.72 m ³
SPL2	- Retaining Wall & Concrete Barrier	: 112.32
SPL3	- Open Lined Canal & Catch Basin	: 31.766 m ³
SPL4	- Chute & Apron	: 3.481 m ³
SPL5	- Information Signage	: 7.00 units

Project Duration : 250 Calendar Days

Done this 29th day of June, 2016 at Koronadal City, Philippines.

Very truly yours,

AMALIA J. DATUKAN, MBA
 Regional Executive Director

Conformed:

 Printed Name and Signature
 Date : 6-29-16

Prepared by:

MONINA M. SALENDAB
 Head, BAC Secretariat