



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
 Regional Field Office XII
 Regional Center, Brgy. Carpenter Hill
 Koronadal City
 Tel. No./Fax No. : 083-228-3413/228-3411

NOTICE TO PROCEED/DELIVER

THE PROPRIETOR
Better Work Construction
 Blk. 3, Triniville Subd.
 Koronadal City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting of Junction National Highway Koronadal Proper - Talcon FMR in Brgy. Koronadal Proper/Talcon, Polomolok/Tupi, South Cotabato with Reference No. 3824340** in the amount of **Thirty-Two Million Three Hundred Forty-One Thousand Nine Hundred Sixty-Six Pesos and 27/100 Only (Php32,341,966.27)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following project Description and Scope of Works, to wit:

Project Description : Concreting of 3.331818 km. road (*Line1 - 2.32455 km at 5.0 lm and Line2 - 993.63 lm at 6.10 lm width*) at 20cm thickness with 1.50 l.m. road shouldering on both sides, Construction of RCP Cross Drainage Structures and slope protection structures

Scope of Works:

PCCP Segment 1

- SPCL "A" - Information Sign Board : 1 l.s.
- Item 100 (2) - Clearing and Grubbing : 1 l.s.
- Item 101 - Removal of Existing 1 line 610mm dia RCPC Structure: 1 l.s
- Item 103(6) - Structure Excavation (910mm dia including Headwall) : 271.62 m³
- Item 500(1) - Pipe Culvert 910mm dia : 34 l.m.
- SPCL "B" - Structural Concrete Class "A" (RCPC Headwall with grouted riprap outfall) : 36.58 m³
- Item 103(3) - Foundation Backfill : 157.14 m³
- Item 102(2) - Surplus Common Excavation : 24,628.56 m³
- Item 104(1) - Embankment : 6,522.59 m³
- Item 105(1) - Sub grade preparation : 19,971.94 m²
- Item 201 - Aggregate Base Course : 5,877.17 m³
- Item 311 - Portland Cement Concrete Pavement: 11,603.56 m²

PCCP Segment 2

- SPCL "A" - Information Sign Board : 1 l.s.
- Item 102(1) - Roadway Excavation (rocky materials) : 4,524.33 m³
- Item 104(1) - Embankment : 885.40 m³
- Item 105(1) - Sub grade preparation : 9,638.21 m²
- Item 201 - Aggregate Base Course : 2,732.48 m³
- Item 311 - Portland Cement Concrete Pavement : 6,061.14 m²
- Item 405(2) - Class "B" Concrete Topping : 2.91 m³

SLOPE PROTECTION



Item 103(6)	- Structure Excavation	: 330 m ³
Item 505(5)	- Grouted Riprap Class "A"	: 160 m ³
Item 103(3)	- Foundation Backfill	: 264 m ³

Project Duration : 295 Calendar Days


Location : Brgy. Koronadal Proper/Talcon, Polomolok/Tupi, South Cotabato

Donethis 27th day of June, 2016 at Koronadal City, Philippines.

Very truly yours,


AMALIA J. DATUKAN, MBA.
Regional Executive Director



Conformed:


EWER ROGEL CLARETE

Printed Name and Signature

Date : JUNE 27, 2016

Prepared by:


MONINA M. SALENDAB
Head, BAC Secretariat