



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
 Regional Field Office XII
 Brgy. Carpenter Hill, General Santos Drive
 Koronadal City
 Tel. No./Fax No. : 083-520-0460

NOTICE TO PROCEED/DELIVER

THE PROPRIETOR
Freden Construction
 Zone 7, Blk. 8, Brgy. Fatima
 General Santos City

Sir/Madam:

Having entered into a contract with the Department of Agriculture, Regional Field Office No. 12, Koronadal City, you are authorized to proceed the **Concreting of Purok Guadalupe, Conel - Purok 3, San Vicente Olympog FMR in Brgy. Olympog, General Santos City with Reference No. 3618626** in the amount of **Twenty-Four Million Two Hundred Fifty-Two Pesos and 45/100 Only (Php24,000,252.45)**, subject to the terms and conditions of the contract specifically the provision on Liquidated Damages (LD) as stipulated in RA 9184, with the following project Description and Scope of Works, to wit:


Project Description : Concreting of 3,331 l.m. Concrete Road at 5.0 l.m. width and 20cm thickness with programmed road shouldering on both sides, Construction of 938.20 l.m. Open Lined Canal, Installation of RCP Cross Drainage Structures


Scope of Works:


Item 100-3	- Individual Removal of Trees, small	: 19 pcs
Item 101-1A	- Removal of Existing Headwall	: 2 units
Item 101 -1B	- Removal of Existing open lined canal	: 6 l.m.
Item 103	- Structure Excavation	: 1,022.77 m ³
Item 102-2	- Roadway Excavation (Surplus Common)	: 8,384.00 m ³
Item 104	- Embankment	: 6,552.00 m ³
Item 105	- Sub Grade Preparation	: 23,177.00 m ²
Item 201	- Aggregate Base Course	: 5,957.10 m ³
Item 311	- Portland Cement Concrete Pavement	: 16,568.50 m ²
Item 404	- Reinforcing Steel	: 4,959.14 kg.
Item 405	- Structural Concrete	: 63.78 m ³
Item 500-A	- Pipe Culvert & Storm Drains 18" Ø	: 6l.m.
Item 500-B	- Pipe Culvert & Storm Drains 24" Ø	: 8 l.m.
Item 500-C	- Pipe Culvert & Storm Drains 36" Ø	: 23 l.m.
Item 506	- Stone Masonry	: 34.23 m ³
Item 508	- Hand Laid Rock Embankment	: 12.52 m ³
SPL 1	- Open Lined Canal	: 938.20 l.m.
SPL 2	- Painting Works	: 17.64 m ²
SPL 3	- Plastering	: 888.30 m ²
SPL 4	- formworks	: 810 bd ft.
SPL 5	- Construction of Signages	: 8 units

Project duration : 250 calendar days
 Location : Barangay Olympog, General santos City

Done this day of **MAR 21 2016** , 2016 at Koronadal City, Philippines.

Very truly yours,

AMALIA J. DATUKAN, MBA.
 Regional Executive Director

Conformed:

FREDDIE M. LAPADA
 Printed Name and Signature
 Date : 3-21-16

Prepared by:

MONINA M. SALENDAB
 Head, BAC Secretariat